



REPUBLIC OF THE PHILIPPINES
DEPARTMENT OF BUDGET AND MANAGEMENT
 GENERAL SOLANO ST., SAN MIGUEL, MANILA

SUPPLEMENTAL/BID BULLETIN (SBB) NO. 1


This SBB No. 1 dated October 30, 2018 for the Project, "Replacement of Basketball Gym Flooring," is issued to clarify, modify or amend items in the Bidding Documents. Accordingly, this shall form an integral part of said Documents.

PARTICULARS			AMENDMENTS/CLARIFICATIONS			
Section VI. Schedule of Requirements			Section VI. Schedule of Requirements			
	Schedule of Requirements	Delivery Date		Schedule of Requirements	Delivery Date	
1	Supply and Delivery of Materials	80 Calendar Days from receipt of the NTP		The Contractor shall provide the materials, tools, equipment, manpower, and supervision needed for the project.	125 Calendar Days from receipt of the NTP	
2	Demolition Works	45 calendar days from delivery materials	1		Supply and Delivery of Materials	80 Calendar Days from receipt of the NTP
3	Installation of new basketball court flooring	45 calendar days from delivery materials	2		Demolition Works	45 calendar days from delivery materials
			3	Installation of new basketball court flooring	45 calendar days from delivery materials	
			<p>Note: Demolition works will only proceed once all the required materials, tools and equipment needed for the project are delivered to the project site.</p> <p>Attached is the Revised Section VI. Schedule of Requirements</p>			

PARTICULARS	AMENDMENTS/CLARIFICATIONS
<p>Section VII. Technical Specifications</p> <p>2</p> <p><u>INSTALLATION OF NEW BASKETBALL COURT</u></p> <p><i>Scope of Work:</i></p> <ul style="list-style-type: none"> •Leveling of sub-base concrete floor •Installation of new basketball court flooring per FIBA standard for Levels 1 and 2, and EN 14904:2006 (European Standard for sports flooring) •Painting of court/game lines for basketball and volleyball •Painting of DBM Logo at the Center of the Court, same size and design as existing •Installation of new analog aluminum threshold for the border of wooden court and concrete floor <p><i>Specifications:</i></p> <p><u>Main Floor</u></p> <ul style="list-style-type: none"> •Thickness (Minimum): 22mm •Type: Treated solid hardwood boards (termite resistant, water resistant, moisture resistant, fire resistant) compliant with EN 14904:2006 standards •Color: Hevea •Finish: High Gloss •Installation type: Tongue and Groove <p><u>Sub Floor</u></p> <ul style="list-style-type: none"> •Construction: Laminated wood Batten System •Thickness (Minimum): 20mm •With high quality shock pads <p>Warranty (excluding normal wear and tear)</p> <ul style="list-style-type: none"> •Five (5) years 	<p>Section VII. Technical Specifications</p> <p>2</p> <p><u>INSTALLATION OF NEW BASKETBALL COURT</u></p> <p><i>Scope of Work:</i></p> <ul style="list-style-type: none"> •Leveling of sub-base concrete floor •Installation of new basketball court flooring per FIBA standard for Levels 1 and 2, and EN 14904:2006 (European Standard for sports flooring) •Painting of court/game lines for basketball, and volleyball and 3 badminton game areas •Painting of DBM Logo at the Center of the Court, same size and design as existing •Installation of new analog aluminum threshold for the border of wooden court and concrete floor or equivalent <p><i>Specifications:</i></p> <p><u>Main Floor</u></p> <ul style="list-style-type: none"> •Thickness (Minimum): 22mm •Type: Treated solid hardwood boards (termite resistant, water retardant, moisture resistant, fire retardant) compliant with EN 14904:2006 standards •Color: Hevea •Finish: High Gloss, Polyurethane Oil Base Finish with wood sealer •Installation type: Tongue and Groove <p><u>Sub Floor</u></p> <ul style="list-style-type: none"> •Construction: Laminated wood Batten System or equivalent •Termite resistant •Water retardant or Marine wood •Thickness (Minimum): 20mm •With high quality shock pads or equivalent <p>Warranty for main floor, subfloor and shock pads (excluding normal wear and tear)</p> <ul style="list-style-type: none"> •Five (5) years
	<p>Attached is the Revised Section VII. Technical Specifications</p>

Other matters:

- The “No Contact Rule” shall be strictly observed. Bidders are not allowed to call or talk to any member of the Bids and Awards Committee, Technical Working Group or Secretariat effective November 6, 2018 right after the opening of bids.
- For guidance and information of all concerned.



CLARITO ALEJANDRO D. MAGSINO

Assistant Secretary

Chairperson, DBM-BAC

Section VI. Schedule of Requirements (Revised)

The delivery schedule expressed as weeks/months stipulates hereafter the date of delivery to the project site.

Item	Description	Delivery Date
	The Contractor shall provide the materials, tools, equipment, manpower, and supervision needed for the project.	125 calendar days from receipt of the NTP
1	Supply and Delivery of Materials	
2	Demolition Works	
3	Installation of new basketball court flooring	

Note: Demolition works will only proceed once all the required materials, tool and equipment needed for the project are delivered to the project site.

I hereby certify to comply and deliver all the above requirements.

Name of Company/Bidder

Signature over Printed Name of Representative

Date

Section VII. Technical Specifications (Revised)

Bidders must state here either "Comply" or any equivalent term in the column "Bidder's Statement of Compliance" against each of the individual parameters of each "Specification."

Item	Specification	Bidder's Statement of Compliance
1	DEMOLITION WORKS	
	Scope of Work: <ul style="list-style-type: none"> • Removal and hauling of existing basketball court flooring • Clearing, cleaning, and leveling of sub-base flooring 	
2	INSTALLATION OF NEW BASKETBALL COURT FLOORING	
	Scope of Works <ul style="list-style-type: none"> • Levelling of sub-base concrete floor • Installation of new basketball court flooring per FIBA standard for Levels 1 and 2, and EN 14904:2006 (European Standard for sports flooring) • Painting of court/games lines for basketball, Volleyball, and 3 badminton game areas • Painting of DBM Logo at the Center of the Court, same size and design as existing • Installation of new analok aluminum threshold for the border of wooden court and concrete floor or equivalent Specifications <p><u>Main Floor</u></p> <ul style="list-style-type: none"> • Thickness (Minimum): 22mm • Type: Treated solid hardwood boards (termite resistant, water retardant, moisture resistant, fire retardant) compliant with EN 14904:2006 standards • Color: Hevea • Finish: High Gloss, Polyurethane Oil Base Finish with wood sealer • Installation type: Tongue and Groove <p><u>Sub Floor</u></p> <ul style="list-style-type: none"> • Construction: Laminated wood Batten System or equivalent • Termite resistant • Water retardant or Marine wood • Thickness (Minimum): 20mm • With high quality shock pads or equivalent 	

	Warranty for main floor, subfloor and shock pads(excluding normal wear and tear): 5 years	
--	---	--

I hereby certify to comply with all the above Technical Specifications.

Name of Company/Bidder

Signature over Printed Name of Representative

Date